



P.O. Box 383258
Germantown, TN 38183
Phone: (901) 207-6573
Email: sales@lockersmfg.com

Preparation Instructions

Any loose items like slope tops and ends should be laid on the floor, do not stack or lean them up against walls.

Check all materials completely as soon as they arrive on site. Check items against packing list and layouts provided. If you are missing any items or the product is damaged, please contact your dealer immediately.

Before beginning the locker installation process, a complete inspection of the job site should be performed. All areas in which lockers will be placed should be inspected. Make sure to check for any variations in the walls and floor surfaces.

Any variations in the walls that the lockers will be attached to should be addressed prior to beginning the installation process.

If lockers were ordered with a base, the base will be able to float over any low spots in the floor. Shimming may be required to ensure that the base sits evenly and securely on the floor.

Make sure the area is clean and free on any debris. If the installation of the lockers is directly to the floor, be sure to sweep the area clean of the debris before beginning.

Once the site inspection and any preparations are completed, the installation process is ready to begin.